












| PLANT SCHEDULE | | | |
|---|-------|--|-------------------|
| TREES | QTY | BOTANICAL NAME | SIZE |
|  | 17 | CORNUS MAS Cornelian Cherry Dogwood | 1.5" CAL, 8-9' HT |
|  | 19 | RHAMNUS PURSHIANA Cascara | MIN 8' HT |
|  | 8 | THUJA PLICATA 'EXCELSA' Western Red Cedar | MIN 8' HT |
| SHRUBS | QTY | BOTANICAL NAME | SIZE |
|  | 17 | AMELANCHIER ALNIFOLIA Serviceberry | 5 GAL, 24" HT |
|  | 71 | BERBERIS DARWINII Darwin Barberry | 5 GAL, 24" HT |
|  | 53 | MAHONIA AQUIFOLIUM Common Barberry | 5 GAL, 36" HT |
|  | 98 | MORELLA CALIFORNICA California Wax Myrtle | 5 GAL, 36" HT |
|  | 28 | PHYSOCARPUS CAPITATUS Pacific Ninebark | 5 GAL, 36" HT |
|  | 86 | VACCINIUM OVATUM Evergreen Huckleberry | 5 GAL, 36" HT |
| GROUND COVERS | QTY | BOTANICAL NAME | SIZE |
|  | 1,150 | GAULTHERIA SHALLON Salal | 2 GAL @ 24" OC |
|  | 619 | POLYSTICHUM MUNITUM Western Sword Fern | 2 GAL @ 36" OC |

- NOTES:
- TREE HEIGHT RESTRICTED THROUGHOUT DUE TO PROXIMITY OF OVERHEAD UTILITY LINES.
 - SEE DRAWING S-126-C1 FOR CIVIL SITE PLAN.
 - NO SIGNIFICANT TREES EXIST ONSITE.
 - NO TREES ON ADJOINING PROPERTIES SHALL BE DIRECTLY AFFECTED BY PROJECT ACTIVITIES.
 - CONTRACTOR IS RESPONSIBLE FOR CONFIRMING LOCATION OF ALL UTILITIES.
 - ALL PLANTING AREAS SHALL BE IRRIGATED WITH A PERMANENT AUTOMATIC IRRIGATION SYSTEM.
 - PLANT MATERIAL LOCATIONS SHALL BE ADJUSTED TO AVOID CONFLICTS WITH SPRINKLER IRRIGATION HEADS.
 - PLANTING BEDS SHALL RECEIVE 4" DEPTH OF COARSE BARK MULCH.
 - FIELD STAKE PLANTING LAYOUT FOR APPROVAL BY THE DISTRICT PRIOR TO PLANTING.
 - ANY DISCREPANCIES BETWEEN THE DRAWINGS AND/OR SPECIFICATIONS AND SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE DISTRICT PRIOR TO PROCEEDING WITH CONSTRUCTION.
 - PLANTING PLAN TAKES PRECEDENCE WHEN THERE IS A DISCREPANCY BETWEEN PLANT QUANTITIES IN THE PLANT SCHEDULE AND THE PLAN.
 - GROUND COVER CONTINUES UNDER TREE AND PLANT SYMBOLS.
 - ALL PLANT MATERIALS SHALL BE INSPECTED BY THE DISTRICT PRIOR TO INSTALLATION.
 - ALL PLANT MATERIAL TO BE FULL AND WELL-ROOTED.
 - ALL TREES AND SHRUBS TO BE WELL-BRANCHED.
 - ALL TREES TO HAVE STRAIGHT CENTRAL LEADER, SINGLE TRUNK, AND SYMMETRICAL BRANCHING.



| | | |
|--|-----------|------|
| ENGR | CHKR | APVD |
| DESCRIPTION | | |
| ENGR | CHKR | APVD |
| REVISIONS | | |
| No | DATE | BY |
| DESCRIPTION | | |
| STATE OF WASHINGTON LANDSCAPE ARCHITECT <i>Masatoshi Yamaguchi</i> MASATOSHI YAMAGUCHI LICENSE NO. 371 EXPIRES ON 8-24-17 | | |
| SNOHOMISH COUNTY PUD PUBLIC UTILITY DISTRICT NO 1 | | |
| WO | 100001443 | |
| TASK | | |
| SCALE | NOTED | |
| DFTR | KJ | |
| CHKR | | |
| ENGR | | |
| APVD | | |
| DATE | 12/05/16 | |
| EAGLE CREEK SUBSTATION LANDSCAPE PLAN | | |
| REV | DRAWING | |
| 0 | S-126-KL1 | |